SCHEDULE - B

Name of the Work: Construction of drain 1st and 2nd main RMV 2nd Stage in Ward No. 18

Indent No: 9980

Sl. No	Description of item	Unit	Qty	Rate (Rs)	
				In figures	In words
1	Dismantling of existing strutures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metrs complete as per specifications. i) Lime / Cement Concrete. I. By Manual Means : A. Lime Concrete, cement concrete grade M-10 and below. MORTH Specification No.202 Page No.147. I No.18.17 PWDSR - 2013-14	Cum	108	240.0	Rupees Two Hundred Forty Only
2	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in ordinary soil not exceeding 1.5 m. in depth including sressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications. specification No. KBS 2.1 (b) / 2.3.5. P No.5 I No. 2.4 PWDSR - 2013-14	Cum	90	145.0	Rupees One Hundred Forty Five Only
3	Providing and laying in position plain cement concrete of mix M 7.5 with OPC cement @ 180 kgs using 40mm and down size graded granite metal CA @ 0.85 cum and FA @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM machinery, curing complete as per specifications. Specification No.KBS 4. 1,4.2 P No. 12 I no 4.3 PWDSR - 2013-14	Cum	45	4100.0	Rupees Four Thousand One Hundred Only
4	Providing and constructing grabute / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications. KBS 5.1.13 Page No.26. I No.5.12 PWDSR - 2013-14	Cum	108	4101.0	Rupees Four Thousand One Hundred One Only

Contractor

Executive Engineer (Hebbal)
Bruhat Bangalore Mahanagara Palike

Sl. No	Description of item	Unit	Qty	Rate (Rs)	
				In figures	In words
5	Providing and laying in position plain cement concrete of nominal mix M 15 with cement @ 240 kgs using 20mm and down size graded granite metal, CA @ 0.878 cum FA @ 0.459 cum and machine mixed, concrete laid in layers not exceeding 15 cms. Thick, well compacted in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Page No.12. I N0.4.6 PWDSR - 2013-14	Cum	18	4400.0	Rupees Four Thousand Four Hundred Only
6	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, incluing cost of materials, labor, curing complete as per specifications. Page No.122. I No.15.3 PWDSR - 2013-14	Sqm	240	75.0	Rupees Seventy Five Only
7	Providing an laying in position reinforced cement concrete of nominal mix M 20 with OPC @ 320 kgs with 20mm and down size graded granite metal, CA @ 0.878 cum and FA @ 0.459 cum and super palstisizer @ 3 ltr confirming to is 9103-1999 reaffirmed 2008 machine mixed, concrete laid in layers not exceeding 15 cms thick, vibraited for all works in foundation plinth and ground floor level for retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, butresses, string or lacing courses, parapets, coping, bed blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No.KBS 4.1, 4.6 P No.13. I No. 4.11 PWDSR - 2013-14	Cum	9	5500.0	Rupees Five Thousand Five Hundred Only
8	Providing and laying position reinforced cement concrete covering slabs madeout of mix 1:1.50:3 with 20mm and down size granite metal mixed concrete laid in layers not exceeding 15cms vibrated including cost of materials, labor curing providing and laying in position including transportation complete as per specification. (SLAB THICKNESS OF 10CMS)	Sqm	300	1350.0	Rupees One Thousand Three Hundred Fifty Only
9	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. of size 450 x 200 x 400 mm P 24 I NO.5.29.1 PWDSR - 2013-14	Nos	445	296.0	Rupees Two Hundred Ninety Six Only

Contractor

Executive Engineer (Hebbal)
Bruhat Bangalore Mahanagara Palike

Sl. No	Description of item	Unit	Qty	Rate (Rs)	
				In figures	In words
10	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plasered concrete surfaces, with materials, labour compete as per specifications. Specification No.KRBS 800.3 MORT & H Specification No.800. P No. 195. I no 24.1 PWDSR - 2013-14	Sqm	60	45.0	Rupees Forty Five Only
11	Cost of Haulage Excluding Loading and Unloading MORTH Chapter 1 (Lead chart enclosed)	Cum	180	91.0	Rupees Ninety One Only

Contractor

Executive Engineer (Hebbal)
Bruhat Bangalore Mahanagara Palike